

S90+ cabinet

Perfect workflow at maximum speed with consistent quality.

Brilliant results in a production line - the 3D printer standalone or for a fully automatic production line of your 3D printed parts.

The S90+ is a heavy use unit that does not compromise quality. The automated part separation module (ASM) (patents pending) collects multiple print jobs in an integrated catch tank, eliminating the need for constant attention from a human operator. The S90+ is capable of working 24/7, without breaks, to push your company to the next level.

Performance parameters	S90+ cabinet
Building area	232 × 137 mm
Native pixel	+/- 22,5 µm
Max. part height	150 mm
Light source	405nm, ultra high power UV LED
Resolution	2560 × 1520 px
Dimension (W × H × D)	625 × 1593 × 800 mm
Connections	TCP/IP, USB
Control	10" touch-screen
Versions	Stand-Alone Conveyor (Specifications on request)



Automatic Separation Module (ASM)



Optional with cabinet or conveyor belt



Industrial continuous manufacturing